

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02200-00-00  
Spot: S2N2NWSW Sec/Twnshp/Rge: 17-11S-17W  
2220 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: HADLEY Well #: D-8  
County: ELLIS Total Vertical Depth: 3420 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1134	0	w/450 sxs cmt
L1	2.875	3320	0	w/265 sxs cmt
PROD	4.5	3420	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2010 9:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1314

Proposed Plugging Method: Ordered 125 sxs 60/40 pozmix - 4% gel.  
Squeezed 1976 from 1545' - 1550' w/850 sxs.  
PBTD 3375'. Junk in the hole.  
Lease worked up by Pat Staab.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2010 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with 1" tubing to 3167'.  
Allied rigged to tubing and pumped 50 sxs cement.  
Pulled tubing to 1584'. Allied rigged to tubing and pumped 30 sxs cement to circulate to pit.  
Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sxs - cement circulated up 8 5/8" casing.  
Rigged to 2 7/8" tubing and pumped 5 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:


Top	Bot	Thru	Comments
3395	3407		ARBUCKLE
3368	3378		ARBUCKLE

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED

NOV 15 2010

Form CP-2/3

KCC WICHITA

NOV 01 2010