

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20940-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 36-13S-32W
1335 feet from N Section Line, 335 feet from E Section Line
Lease Name: NUSS FARMS 36A Well #: 1
County: LOGAN Total Vertical Depth: 4650 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/12/2010 2:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG UNRUH Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 09/12/2010 3:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2425' w/25 sxs.
2nd. Plug at 1376' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04

Signed 
(TECHNICIAN) CM

RECEIVED
SEP 20 2010
KCC WICHITA

Form CP-2/3

SEP 15 2010