

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01951-00-01
Spot: SWNENE Sec/Twnshp/Rge: 16-9S-21W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: DRUMM COMMISSION CO. Well #: 4
County: GRAHAM Total Vertical Depth: 3674 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	384	0	375 SX
PROD	6	3668	0	300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2010 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: JERRY WIRTZ Company: NOBLE ENERGY, INC. Phone: (281) 872-3100

Proposed Plugging Method: Ordered out 365 sxs 60/40 pozmix - 4% gel - 500# hulls - 17 sxs gel spacer.
Dakota squeeze February 1995 w/200 sxs at 1160'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2010 3:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 2150' and 1650'.
Ran tubing to 3318'. Basic Cementing pumped 17 sxs gel spacer - followed with 80 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1146'. Basic Cementing pumped 120 sxs cement with 300# hulls - cwc.
PTOH. Topped with 10 sxs cement - casing full.
Hooked up to backside - pumped 15 sxs cement.
Max. P.S.I. 150#. Blew hole in 8 5/8".

Perfs:

Top	Bot	Thru	Comments
3648	3674		ARBUCKLE
3564	3567		
3544	3547		
3527	3534		
3513	3518		
3492	3495		
3454	3461		
3438	3444		
3360	3567		LKC

Remarks: BASIC CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED
AUG 02 2010
8-2-10
KCC WICHITA

CONTINENTAL OIL

#4 DRUMM

16-9-21W
SW NE NE

Contr.

GRAHAM

County

E 2174

Comm.


Comp. 4-20-62

IP 120 BOPD & 2 BW/

LANS 3438-3567

OLD Tops	Depth	Datum
LANS	3363	-1189
ARB	3667	-1493
TD	3674	-1500

Casing ORIG COMM 6-4-48; ARB DEPLETED
 10" 384
 6" 3668
 NEW INFO: PB 3659; PERF LANS 'F' 12/3438-44
 'G' 14/3454-61; 'H' 6/3492-95; 'I' 12/3513-18;
 'J' 14/3527-34; 'K' 6/3544-47; 'L' 6/3564-67;
 ACID 500 'L' ZN; SWB 1 1/2 BWP/2 HRS;
 ACID 500 'L' SWB 1 1/4 BW, TREN DRY;
 ACID 1000 'J' COMM W/'I'; SWB 1 1/2 BO & 6 1/2 BWP/2 HRS;
 SWB 'H' 5 BO, NW/2 HRS, NATL
 ACID 500 'H'; SWB 5 BOPH, NW/3 HRS



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS