

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02892-00-01 ;
Spot: SENWSE Sec/Twnshp/Rge: 15-9S-21W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MOREL J Well #: 6
County: GRAHAM Total Vertical Depth: 3722 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	378	0	300 SX
PKR		3684		
PROD	7	3713	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2010 10:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: JERRY WIRTZ Company: NOBLE ENERGY, INC. Phone: (281) 872-3100

Proposed Plugging Method: Ordered out 425 sxs 60/40 pozmix - 4% gel - 600# hulls - 20 sxs gel spacer.
Basic Cementing Company loaded extra total 575 sxs cement.
Fluid level 200'. CIBP at 3670' with one sack cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2010 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 2250' and 1715'.
Bad casing from 695' to 1108'.
Ran tubing to 3404'. Basic Cementing pumped 20 sxs gel spacer - followed with 80 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1845' - pumped 200 sxs cement with 300# hulls.
Pulled tubing to 961' - pumped 145 sxs cement with 100# hulls.
Pulled to 480' - pumped 100 sxs neat cement - cwc..
PTOH. Topped 7" with 20 sxs cement.
Hooked to backside - pumped 30 sxs cement.
Max. P.S.I. 100#. Blew hole in surface pipe.

Perfs:

Top	Bot	Thru	Comments
3713	3722		LKC
3704	3707		LKC
3625	3630		
3603	3610		
3589	3595		
3572	3579		
3551	3554		
3420	3630		ARBUCKLE

Remarks: BASIC CEMENTING COMPANY.

Plugged through: TBG

RECEIVED
AUG 02 2010
8-2-10
KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

CONTINENTAL OIL

#6

MOREL

15-9-21W
SE NW SE

Contr.

GRAHAM

County

E 2249 Comm.


Comp. 4-13-62

IP 76 BOPD, NW/LANS

28 BOPD & 87 BW/ARB

Tops	Depth	Datum
LANS	3418	-1169
ARB	3712	-1463
TD	3722	-1473

Casing
10" 378
7" 3713
2600' OIH/3 HRS: WAS ARB PROD,
12-23-49: NEW INFO: PERF LANS
'H' 6/3551-54: 'I' 14/3572-79
'J' ZN 12/3589-95: 'K' 14/3603-
10: 'L' 10/3625-30: ACID 1500
SET MOD 'D' PKR 3684



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS