

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-19097-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 13-11S-18W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PEAVEY TWIN Well #: 10  
County: ELLIS Total Vertical Depth: 3445 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	453	0	185 SX
PROD 7		3444	0	120 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2010 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY, INC. Phone: (281) 872-3100

Proposed Plugging Method: Ordered out 125 sxs common with 3% c.c. - 275 sxs 60/40 pozmix - 4% gel - 23 sxs gel spacer - 500# hulls.  
DV at 1103' w/220 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2010 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3319'. Basic Cementing pumped 13 sxs gel spacer - followed with 75 sxs common with 3% c.c. with 200# hulls.  
Pulled to 2133' - pumped 10 sxs gel spacer - followed with 50 sxs common with 3% c.c. with 200# hulls.  
Pulled tubing to 1180' - pumped 175 sxs 60/40 pozmix - 4% gel cwc.  
PTOH. Topped 7" casing with 70 sxs.  
Hooked up to backside - 350# instant pressure.

Perfs:

Top	Bot	Thru	Comments
3333	3335		ARBUCKLE

Remarks: BASIC CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN) (M)

AUG 26 2010

RECEIVED  
AUG 30 2010  
KCC WICHITA  
Form CP-2/3

PHILLIPS PET

#10. PEAVEY

13-11-18W  
NE NE SE

Contr. SIERRA PET

(TWIN)

ELLIS County

E 1857 DF Comm. 8/17/62 Comp. 9/20/62 IP 29 BO & 211 BWPB  
ARB 3333-35

LOG Tops	Depth	Datum
HEEB	3008	-1151
TOR	3028	-1171
LANS	3052	-1195
DRUM	3188	-1331
B/KC	3290	-1433
SIMP DOL	3314	-1457
SIMP SH	3322	-1465
ARB	3332	-1475
TD	3445	-1588

Casing 10"453/185 SX  
 NO TSTS 7"3444  
 CO 3430  
 PERF 8/3333-35: SWB 4 BO/PLUS DRLG  
 MUD/5 HRS: ACID 350: SWB 32 BO &  
 136 BW/6 HRS, SWB 12 BO & 8 BW/  
 1 HR

BEMIS-SHUTTS

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS