

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02385-00-00
Spot: NWNE Sec/Twnshp/Rge: 5-12S-17W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SHUTTS B Well #: 5
County: ELLIS Total Vertical Depth: 3636 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1384	0	700 SX
PROD	5.5	3614	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2010 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY, INC. Phone: (281) 872-3100

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 17 sxs gel spacer.
Casing leaks. Squeezed 1428'-2545' w/1050 sxs cement in October 1980.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2010 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1330'.
Ran tubing to 3564'. Basic Cementing pumped 17 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1432'. Basic Cementing pumped 200 sxs cement with 300# hulls.
Pulled tubing to 700' - pumped 100 sxs cement cwc.
PTOH. Topped 5 1/2" casing with 10 sxs cement - casing full.
Hooked up to backside - pumped 10 sxs.
Max. P.S.I. 350#. S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
3614	3636		ARBUCKLE


RECEIVED
AUG 31 2010
KCC WICHITA

Remarks: BASIC CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

AUG 27 2010

double-click in this window to close it
5-12-17M
C NW NE

PHILLIPS PETROLEUM CO. #5 SHUTTS

Contr _____ ELLIS _____ County

E 2129 Comm 10-19-47 Comp 12-26-47 IP 97 BOPD

Tops	Depth	Datum
ANFY	1347	
HEEB	3301	
TORONTO	3319	
LANS	3360	
ARR	3612	
TD	3636	

Casing
8" 1384
5" 3613

DP 3616; wtr
DD 3626
Swb 68 BO/1h hrs
DD 3636, 560' OIH
Swb 39 BO/9 hr

+	+
+	+
+	+
+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS