

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21881-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 8-16S-16W
1752 feet from N Section Line, 576 feet from E Section Line
Lease Name: DOMELIVING TRUST ET AL Well #: 1-8
County: RUSH Total Vertical Depth: 3593 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1083		WITH 425 SX CMT
PROD	5.5	3589	2525	WITH 125 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/21/2010 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3230' & 5 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2010 12:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3205' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1118' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 590' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3456	3459		PENN SAND
3390	3394		LANSING
3282	3286		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
SEP 24 2010
KCC DODGE CITY

RECEIVED
SEP 30 2010
9-30-10
KCC WICHITA