

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01629-00-02
Spot: SENE Sec/Twnshp/Rge: 2-9S-25W
1015 feet from N Section Line, 300 feet from E Section Line
Lease Name: RICHMEIER Well #: A 2
County: GRAHAM Total Vertical Depth: 3955 feet

Operator License No.: 6677
Op Name: SANDLIN OIL CORPORATION
Address: 621 17TH ST STE 2055
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	150	0	w/unknown sxs cmt
PROD	5.5	4064	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2010 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY SANDLIN Company: SANDLIN OIL CORPORATION Phone: (303) 292-3313

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 bbls mud spacer.
Tubing stuck in the hole at 3687'.
Perforated at 2225' - 1400' - 200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2010 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3680' - pumped 10 bbls mud spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 50# hulls.
Pulled tubing to 2250' - pumped 100 sxs 60/40 pozmix - 4% gel with 50# hulls.
Pulled tubing to 1406' - pumped 130 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 40 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Remarks: ALLIED CEMENTING COMPANY-TICKET #30807.

Plugged through: TBG

RECEIVED
SEP 03 2010
KCC WICHITA

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

EMPIRE DRLG #2 RICHMEIER 'A' 2-9-25W SE NE NE

Contr. EMPIRE DRLG GRAHAM County

E2536 RB Comm. Comp. 11-17-61 IP 97 BOPD/LANS

LOG Tops	Depth	Datum	Casing
HEEB	3806	-1270	8" 150
TOR	3831	-1295	5" 4064
LANS	3847	-1311	DST 3865-85/1 HR, G/40", 1980' o, 240' OILY SW, BHP 1120-1065#; DST 3838-3905/1 HR, 1800' G, 37' MCO, BHP 1280-1240#/30"; DST 3912-35/1 HR, G/55", 55' OCM, BHP 1180-710#; DST 3925-35/1 HR, G/5", 1410' o, BHP 1160-1090#/30"; DST 3840-68/30", 10' M, BHP 1000-820#; DST 4008-4030/1 HR, G/45", 50' H OILY GCM, 10' o, BHP 60-60#; DST 4030-65/1 HR, 600' G, 180' o & GCM, BHP 410-290#
ZN 2	3876	-1340	
ZN 2A	3889	-1353	
ZN 3	3918	-1382	
ZN 4	3929	-1393	
ZN 5	3940	-1404	
ZN 6	3982	-1446	
ZN 6A	4004	-1468	
ZN 7	4022	-1486	
ZN 8	4042	-1506	
ZN 9	4056	-1520	
TD	4065	-1529	

SHILOH POOL
 CO: PERF 4042-48: BLD M & SSO: ACID 2000:
 SWB 8 BOPH/4 HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS
 4065