

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22440-00-01
Spot: NWSE Sec/Twnshp/Rge: 4-14S-22W
2165 feet from S Section Line, 1950 feet from E Section Line
Lease Name: COFFMAN Well #: 1
County: TREGO Total Vertical Depth: 4249 feet

Operator License No.: 33839
Op Name: ROBERT HOPKINS OPERATIONS, LLC
Address: 709 HAROLD AVE
SALINA, KS 67401

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204	0	165 SX
T1	2.375	4223		
PROD	5.5	4249	0	400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2010 4:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK STAAB Company: ROBERT HOPKINS OPERATIONS, Phone: (785) 819-2460

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel.
DV Tool at 1777'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2010 7:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4219' - pumped 16 sxs gel - followed with 50 sxs cement and 300# hulls.
Pulled tubing to 1800' - pumped 125 sxs cement with 200# hulls.
Pulled tubing to 900' - pumped 50 sxs cement.
Pulled out - topped off with 15 sxs cement.
Tied onto backside and pumped 15 sxs cement.
Max. P.S.I. 500#. Shut in.

Perfs:


Top	Bot	Thru	Comments
4236	4238		
4217	4221		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35141A.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

NOV 15 2010

Form CP-2/3

NOV 02 2010

KCC WICHITA