

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03369-00-00
Spot: NENENE Sec/Twnshp/Rge: 20-15S-13W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: HILL Well #: 2
County: RUSSELL Total Vertical Depth: 3290 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	278	0	175 SX
L1	4.5	3284	0	250 SX
PROD	7	3100	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2010 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 587-3936

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls - 6 sxs gel.
Perf: 200' - 500' - 820' - 1550'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2010 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' - pumped 6 sxs gel - followed with 50 sxs cement with 200# hulls.
Pulled tubing to 1550' - pumped 140 sxs cement with 100# hulls - cement circulated.
POOH. Hooked to casing and pumped 20 sxs cement.
Max. P.S.I. 300#. S.I.P. 275#.
Hooked up to Braden head and pumped 50 sxs cement.
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3284	3290		ARBUCKLE OPEN

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #34966.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

RECEIVED

SEP 20 2010

Form CP-2/3

SEP 14 2010

KCC WICHITA