

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-03371-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 20-15S-13W  
4950 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: HILL Well #: 5  
County: RUSSELL Total Vertical Depth: 3343 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY, A GENE  
Address: 4200 E SKELLY DR STE 620  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3060		
SURF	10.75	235	0	150 SX
PROD	5.5	3192	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/28/2010 9:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 793-2299

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 200# hulls - 11 sxs gel.  
Perf: 1500' - 820' - 500' - 150'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/28/2010 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2853' - pumped 8 sxs gel - followed with 25 sxs cement.  
Pulled tubing to 1488' - pumped 80 sxs cement with 200# hulls.  
Pulled tubing to 744' - pumped 220 sxs cement - some circulation on Braden head - cement circulated out the backside.  
POOH. Hooked to casing and pumped 80 sxs cement - some circulation out Braden head.  
Closed casing and hooked to Braden head - pumped 15 sxs cement.  
Max. P.S.I. 400#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3100	3112		LKC

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35122.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN) (M)

RECEIVED

OCT 04 2010

KCC WICHITA

Form CP-2/3

SEP 30 2010