

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01653-00-02)
Spot: NWNESE Sec/Twnshp/Rge: 25-14S-14W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: HICKEY OWWO Well #: 9
County: RUSSELL Total Vertical Depth: 2391 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	242	0	200 SX
PROD	5.5	2391	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2010 8:15 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TODD A. BROWN Company: RUSSELL OIL, INC. Phone: (785) 445-6270

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2010 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing and tagged CIBP at 2290' - pulled 5' (tubing at 2285') - pumped 100 sxs cement with 250# hulls.
Pulled tubing to 1200' - pumped 130 sxs cement with 250# hulls.
Cement circulated - backside and braden head.
POOH. Pumped 15 sxs cement and topped off.

Perfs:

Top	Bot	Thru	Comments
2266	2280		TARKIO

Remarks: ALLIED CEMENTING COMPANY-TICKET #41792.

Plugged through: TBG

District: 04

Signed

Ray A. D. K&D

(TECHNICIAN)

CM

RECEIVED

JUL 15 2010

KCC WICHITA

Form CP-2/3

JUL 13 2010

IVAN HOLT
BOX 401, RUSSELL, KS. #9 HICKEY "OWWO" 25-14-14W
NW NE SE

CONTR IVAN HOLT WELL SERV. CTY RUSSELL

GEOL FIELD HALL-GURNEY

E 1750 CM 7/22/77 CARD ISSUED 10/13/77 IP P 10 BOPD + 70 BWPD
TARK 2335-2339

+	+	+
+	+	+
+	+	+

API NOT ASSIGNED

TOPS	DEPTH	DATUM
1ST TARK	2256	- 506
2ND TARK	2271	- 521
TD	2391	- 641

OLD INFO: OPERATOR WAS CITIES SERVICE
OIL CO. #9 HICKEY; SPD ?, SET 5" 239
COMPLETED FOR 237 BOPD/9/5/52
MIRT - PF 2268-2283, BAIL 105GOPH/
3HRS, SANDFRAC

NEW INFO: MIRT CO TD, PF 2335-2339,
FRAC 10,000# SD + WTR, REC LD, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS