

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20112-00-01
Spot: NENE Sec/Twnshp/Rge: 34-18S-38W
4665 feet from S Section Line, 657 feet from E Section Line
Lease Name: BAUM Well #: 2 SWD
County: WICHITA Total Vertical Depth: 3066 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	328		WITH 250 SX CMT
DVT		1396		WITH 250 SX CMT
PROD	5.5	3066	0	WITH 120 SX CMT

Well Type: SWD UIC Docket No: D27582.0 Date/Time to Plug: 09/23/2010 2:00 PM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: JAMES Company: KELSO, MIKE OIL, INC. Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2010 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SAND TO 2721' & 5 SX CMT. 2ND PLUG TESTED CASING TO 600#. RIPPED HOLE IN 5 1/2" @ 1604'. PUMPED 200 SX CMT. (ESTIMATE 50 SX CMT OUT HOLE) MAXIMUM PRESSURE 600#. SHUT IN PRESSURE 600#. 3RD PLUG PUMP 15 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. SHUT IN PRESSURE 300#.

Perfs:

Top	Bot	Thru	Comments
2787	2793		


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
OCT 22 2010
KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

OCT 13 2010

KCC DODGE CITY

Form CP-2/S