

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23211-00-00
Spot: S2SESENE Sec/Twnshp/Rge: 24-21S-13W
2585 feet from N Section Line, 330 feet from E Section Line
Lease Name: FREEMAN MCFADDEN Well #: 1-24
County: STAFFORD Total Vertical Depth: 3800 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3240		WITH 2 SX CMT
CIBP		3645		
CIBP		3690		
SURF	8.625	275		WITH 275 SX CMT
PROD	4.5	3788	2400	WITH 290 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2010 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TIM HOSS Company: MULL DRILLING Phone: (620) 594-2403

Proposed Plugging Method: SET CIBP @ 3240' WITH 2 SX CMT. PLUG AT 750' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2010 10:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3240' WITH 2 SX CMT. OPERATOR WAS PULLING OILY, WET JOINTS OF PIPE SO THEY PUMPED 20 SX GEL @ 1500'. 1ST PLUG AT 750' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3702	3710		
3666	3670		
3650	3670		
3498	3504		
3478	3486		
3464	3468		
3441	3448		
3336	3340		
3323	3326		
3298	3310		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED

AUG - 2 2010

KCC DODGE CITY

Signed

Eric MacLaren

RECEIVED
STATE CORPORATION COMMISSION
(TECHNICAL)

AUG 09 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3