

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25151-00-00
Spot: NWSWNWSE Sec/Twnshp/Rge: 30-16S-22W
1778 feet from S Section Line, 2580 feet from E Section Line
Lease Name: JONES UNIT Well #: 1-30
County: NESS Total Vertical Depth: 4530 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	217		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/16/2010 2:15 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: JAY SCHNEIDER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 09/16/2010 4:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed Richard W. Lacey

RECEIVED
SEP 22 2010
KCC DODGE CITY

RECEIVED (TECHNICIAN)
SEP 27 2010
KCC WICHITA

Form CP 200