

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-00876-00-00  
Spot: NENESE Sec/Twnshp/Rge: 23-31S-9W  
2319 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MARTIN Well #: 1  
County: HARPER Total Vertical Depth: 4381 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 12  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4320		
SURF	8.625	221	0	150 SX
PROD	5.5	4381	2802	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2945

Proposed Plugging Method: PER KCC REQUIREMENTS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/30/2010 6:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

CIBP @4320 AND 5 SXS CEMENT. CASING CUT OFF AT 2802' AND PULLED TO 1426' - -35 SXS OF CEMENT SPOTTED, CASING PULLED TO 953' & 35 SXS OF CEMENT SPOTTED. CASING PULLED TO 346' AND CEMENT CIRCULATED TO SURFACE WITH 175 SXS OF CEMENT.

Top	Bot	Thru	Comments
4368	4376	CSG	

RECEIVED  
OCT 01 2010  
KCC WICHITA

Remarks: COPELAND OUT OF GRET BEND. TICKET #34791 -- 60/40 4% GEL - POS MIX

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)