

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21120-00-02  
Spot: NENE Sec/Twnshp/Rge: 3-29S-20W  
4678 feet from S Section Line, 509 feet from E Section Line  
Lease Name: HAYSE A Well #: 1  
County: KIOWA Total Vertical Depth: 5475 feet

Operator License No.: 33388  
Op Name: J. MARK RICHARDSON FAMILY TRUST  
Address: 1406 N CHARLES  
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	634		WITH 385 SX CMT
PROD	4.5	5474	2415	WITH 270 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/06/2011 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT AT 4390'. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/06/2011 4:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 400# HULLS & 30 SX CMT AT 4390'. 1ST PLUG AT 1200' WITH 100# HULLS, 15 SX GEL & 50 SX CMT W/3% CC. 2ND PLUG AT 660' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5398	5404		
4652	4656		
4620	4624		
4592	4598		
4391	4397		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Jerry W Stapleton*  
PIRETT

(TECHNICIAN)

RECEIVED

JAN 10 2011

KCC DODGE CITY

KANSAS CORPORATION COMMISSION

Form CP-243

JAN 12 2011

RECEIVED