

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21654-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 20-33S-2E
4350 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HOWER Well #: 2
County: SUMNER Total Vertical Depth: 3648 feet

Operator License No.: 3954
Op Name: JAED PRODUCTION CO., INC.
Address: PO BOX 902
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	253		175 SX
PROD	4.5	3648	1200	150 SX

Well Type: EOR UIC Docket No: E26394.5 Date/Time to Plug: 11/05/2010 12:00 PM
Plug Co. License No.: 33556 Plug Co. Name: DRAKE EXPLORATION, LLC
Proposal Rcvd. from: DARRIN BROYLES Company: JAED Phone: (620) 441-7223

Proposed
Plugging
Method:

SET CIBP 50' ABOVE THE TOP PERFS, REC. CASING. RUN TUBING TO 300' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 11/05/2010 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3000' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1200' AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 300', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3270	3278	CSG	

Remarks: CONSOLIDATED CMTG #29939 60/40 4% GEL

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

DEC 15 2010

KCC WICHITA