

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22463-00-00
Spot: E2SENE Sec/Twnshp/Rge: 33-19S-12W
1980 feet from N Section Line, 330 feet from E Section Line
Lease Name: MUSENBERG B Well #: 2
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.62	310	0	225 SX CMT
PROD	5.5	3448	0	157 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2010 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: K&N PETROLEUM, INC. Phone: (620) 793-6005

Proposed Plugging Method: Emergency plug - casing parted.
Pulled tubing and rods. Ran in with perf gun - shot perfs at 1470' - 670' - 260'.
Ran in with tubing - casing parted at 2000'.
Will plug from 2000'.
Ordered 500 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 1980' - tied to tubing and pumped 125 sxs cement - no returns.
Pulled to 1400' - pumped 100 sxs cement - no returns.
Pulled to 670'. Shut down for one hour - tied to tubing and pumped 175 sxs cement
with 550# hulls - 3% c.c. - circulated cement to surface.
Pulled tubing and topped off with 20 sxs cement.
Tied to surface pipe and pumped 10 sxs cement - cement circulated back up casing - shut in.

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED Form CP-2/3

DEC 30 2010

DEC 28 2010

KCC WICHITA