

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20682-00-00
Spot: SESE Sec/Twnshp/Rge: 19-31S-40W
666 feet from S Section Line, 640 feet from E Section Line
Lease Name: SMITH E Well #: 19-2
County: MORTON Total Vertical Depth: 5550 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: PO BOX 1330 REGULATORY GROUP
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1595		WITH 820 SX CMT
PROD	5.5	5550	1585	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/03/2011 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 250# HULLS & 25 SX CMT TO BOTTOM. PLUG AT 1630' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/03/2011 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 250# HULLS & 25 SX CMT AT 5019'. 1ST PLUG AT 1585' WITH 50 SX CMT.
2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5019	5050		UPPER MORROW

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

JAN - 4 2011

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 21 2011

CONSERVATION DIVISION
WICHITA, KS