

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10105-00-01
Spot: N2SENE Sec/Twnshp/Rge: 27-25S-14W
3649 feet from S Section Line, 691 feet from E Section Line
Lease Name: KIPP A Well #: 2
County: STAFFORD Total Vertical Depth: 3889 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1930		WITH 2 SX CMT
SURF	10.75	366		WITH 250 SX CMT
PROD	4.5	2176	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/06/2011 4:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL Phone: (785) 623-4081

Proposed
Plugging
Method:

SET CIBP @ 1920' & 2 SX CMT. RUN BOND LOG, PRESSURE TEST, & THEN PLUG WELL.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/07/2011 9:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 1930' WITH 2 SX CMT ON TOP OF PLUG WITH DUMP BAILER. LOADED HOLE & RAN BOND LOG. TOC=1470'. PRESSURED CASING TO 300 PSIG & HELD. PERFORATED 4 1/2" @ 930'. PUMPED 400 SX 60/40 POZMIX 4% GEL FOLLOWED BY 175 SX COMMON CMT DOWN 4 1/2". GOOD CIRCULATION UP 10 3/4" X 4 1/2" ANNULUS BUT NO CMT. RAN OUT OF CMT & SDON. 1/7/11: TAGGED CMT INSIDE 4 1/2" CASING @ 183' WITH TBG. PUMPED 25 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 4 1/2" CASING. PUMPED 50 SX CMT DOWN 10 3/4" X 4 1/2" ANNULUS. PRESSURED TO 500 PSIG. ALL CMT ON 1/7/11 WAS COMMON CMT.

Perfs:

Top	Bot	Thru	Comments
2024	2028		WINFIELD
1992	1996		KRIDER
1970	1974		HERINGTON

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

JAN - 7 2011

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-273

JAN 21 2011

CONSERVATION DIVISION
WICHITA, KS