

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21709-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 17-16S-27W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: ALBIN Well #: 1
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	287		WITH 165 SX CMT
PC		2147		WITH 450 SX CMT TO SURFACE
PROD	4.5	4597	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GERALD WALKER Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS THEN GEL SPACER TO ANHYDRITE. CMT TO SURFACE & 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2010 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT & 200# HULLS, 13 SX GEL IN WATER THEN 215 SX CMT.
MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 100#. TIED ONTO BACKSIDE &
PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4540	4543		CHEROKEE
4521	4526		CHEROKEE
4462	4466		FORT SCOTT
4446	4449		FORT SCOTT
4202	4206		
4114	4118		
4100	4104		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
JAN 10 2011
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)

KANSAS CORPORATION COMMISSION

JAN 12 2011

RECEIVED