

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24776-00-00  
Spot: S2SESE Sec/Twnshp/Rge: 16-18S-15W  
330 feet from S Section Line, 660 feet from E Section Line  
Lease Name: KUHLMAN Well #: 1  
County: BARTON Total Vertical Depth: 3576 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	820	0	450sx
T1	2	3222		
PROD	4.5	3575	1823	200sx

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2011 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2011 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 1823'.  
Pulled casing to 1750' - pumped 100 sxs cement with 200# hulls.  
Pulled casing to 950' - pumped 25 sxs cement with 100# hulls.  
Pulled casing to 500' - circulated cement to surface with 190 sxs cement with 200# hulls.  
Pulled casing - topped off with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3214	3219		

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

KANSAS CORPORATION COMMISSION Form CP-2/3

1-18-11  
JAN 18 2011

RECEIVED

JAN 14 2011