

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23584-00-00  
Spot: S2NESE Sec/Twnshp/Rge: 14-23S-12W  
1650 feet from S Section Line, 660 feet from E Section Line  
Lease Name: MARILYN Well #: 1-14  
County: STAFFORD Total Vertical Depth: 3882 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	348		WITH 350 SX CMT
PROD	5.5	3877	2740	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/30/2010 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK BOTTOM & CAP WITH 5 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 12/30/2010 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SANDED TO 3635' & 5 SX CMT. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT.  
2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3795	3799		
3794	3796		
3690	3700		
3637	3640		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

DEC 30 2010

KCC DODGE CITY

KANSAS CORPORATION COMMISSION

JAN 12 2011

RECEIVED