

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-13076-00-00
Spot: NWSESE Sec/Twnshp/Rge: 19-21S-12W
1023 feet from S Section Line, 984 feet from E Section Line
Lease Name: MCCRARY Well #: 2
County: STAFFORD Total Vertical Depth: 3570 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3320		WITH 4 SX CMT
SURF	10.75	261		WITH 225 SX CMT
PROD	7	3565	364	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2010 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: FIND TD, SET CIBP @ & 4 SX CMT AT 3340'. PERFORATE 7" @ 660'. RUN TBG TO 660'. PUMP 15 SX GEL & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2010 12:54 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

FOUND TD @ 3344'. SET CIBP @ 3320' WITH 4 SX CMT ON TOP WITH DUMP BAILER. CASING CORRODED INTO AT 364'. PULLED 364' OF 7" CASING OUT OF HOLE. WORKED TBG IN WITH MUCH DIFFICULTY TO 670'. PERFORATED 7" @ 672'. PUMPED 15 SX GEL FOLLOWED BY 450 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE. PULLED TBG OUT OF HOLE. HOLE STAYED FULL OF CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

RECEIVED
DEC 30 2010
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
JAN 06 2011
KCC WICHITA

FORM CP 3/3