

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20943-00-00  
Spot: NE Sec/Twnshp/Rge: 2-14S-32W  
1115 feet from N Section Line, 1345 feet from E Section Line  
Lease Name: ARLEN ROSE Well #: 1  
County: LOGAN Total Vertical Depth: 4650 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/24/2010 7:00 PM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: CAROL Company: RAYMOND OIL COMPANY, INC. Phone: (316) 267-4214

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE  
Date/Time Plugging Completed: 09/24/2010 8:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 2335' w/25 sxs.  
2nd. Plug at 1180' w/100 sxs.  
3rd. Plug at 315' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

Remarks: CONSOLIDATED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

OCT 04 2010

Form CP-2/3

SEP 29 2010

KCC WICHITA