

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20764-00-00
Spot: SWSW Sec/Twnshp/Rge: 28-1S-35W
510 feet from S Section Line, 4620 feet from E Section Line
Lease Name: SABATKA Well #: 1
County: RAWLINS Total Vertical Depth: 4450 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	340	0	240 SX
PROD	5.5	4449	0	400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2010 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: ART SCHOENHOEFER Company: RAYMOND OIL COMPANY, INC. Phone: (316) 267-4214

Proposed Plugging Method: Ordered 490 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2010 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 340' w/240 sxs cement.
5 1/2" production casing set at 4449' w/400 sxs cement.
5 1/2" casing perforated at 3124' and 2440'.
Ran tubing to 3100' - pumped 275 sxs cement mixed with 500# hulls.
Pulled tubing to 1550' - pumped 150 sxs cement with 100# hulls - cement circulated to surface.
Pulled tubing to surface.
Connected to 5 1/2" production casing and pumped 25 sxs cement.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.
Braden head ruptured.

Perfs:

Top	Bot	Thru	Comments
4363	4372		
4275	4284		
4223	4230		

Remarks: CONSOLIDATED CEMENT SERVICES-TICKET #28641.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

NOV 15 2010

NOV 01 2010

KCC WICHITA