

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22116-00-01  
Spot: S2S2SE Sec/Twnshp/Rge: 34-9S-22W  
330 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: RECH Well #: 1  
County: GRAHAM Total Vertical Depth: 3995 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	245	0	165 SX CMT
T1	2.375	3797		
DVT		1295		
PROD	4.5	3992	0	200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2010 11:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: MIKE Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel.  
DV Tool at 1295' w/200 sxs.  
Shoot perfs at 2010' - 1100' - 300'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/17/2010 3:30 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 3927' - pumped 8 sxs gel - followed with 80 sxs cement with 200# hulls.  
Pulled tubing to 2020' - pumped 150 sxs cement with 100# hulls - good circulation of cement.  
Pulled tubing out - topped off with 10 sxs cement - full.  
Tied onto backside - pumped 2 1/2 sxs cement.  
S.I.P. 300#.

**Perfs:**

Top	Bot	Thru	Comments
3727	3731		

RECEIVED  
DEC 22 2010  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34051.

Plugged through: TBG

District: 04

Signed   
(TECHNICIAN)

CM

Form CP-2/3

DEC 20 2010