

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06543-00-00
Spot: W2SWNE Sec/Twnshp/Rge: 31-18S-10W
3310 feet from S Section Line, 2336 feet from E Section Line
Lease Name: BUEHLER Well #: 1
County: RICE Total Vertical Depth: 3283 feet

Operator License No.: 30525
Op Name: LANGSTON, D. S.
Address: 310 W CENTRAL STE 202
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	275		
PROD	5.5	3260		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/08/2010 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, SAND PERFS TO 2710' AND CAP WITH 5 SX'S CEMENT. PERFORATE @ 1250', 900' AND 325'. RUN TUBING TO 1250' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 325' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3260	3283	OH	
3005	3050	CSG	
2786	2792	CSG	

Remarks: 60-40 POZ, 4% GEL. ALLIED TICKET #33469. LOG TECH #32266.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED

JAN 03 2011

Form CP-2/3

KCC WICHITA