

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22088-00-00
Spot: N2S2NENE Sec/Twnshp/Rge: 23-27S-5W
810 feet from N Section Line, 660 feet from E Section Line
Lease Name: FASBENDER Well #: 1-23 RE
County: KINGMAN Total Vertical Depth: 4185 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	252		190 SXCMT.
T1	2.875	3629		
PKR		3629		
PROD	5.5	4021	2620	220 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: _____ Phone: _____

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/08/2010 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3690' CAPPED WITH 5 SX CEMENT. CUT CASING OFF AT 2620', PULLED CASING TO 850' SPOTTED 35 SXS OF CEMENT WITH 100# HULLS AND 3% CC, PULLED CASING TO 520' SPOTTED 35 SXS OF CEMENT WITH 100# OF HULLS, PULLED CASING TO 320' CIRCULATED 95 SXS OF CEMENT TO SURFACE, FELL BACK 45' TOPPED OFF WITH 10 SXS OF DRY CEMENT.

Perfs:

Top	Bot	Thru	Comments
3792	3795	CSG	
3776	3782	CSG	
3762	3767	CSG	

Remarks: QUALITY WELL SERVICE, ALSO CEMENTING COMPANY

Plugged through: CSG

RECEIVED
DEC 15 2010

District: 02

Signed B. J. Hope
(TECHNICIAN)

KCC WICHITA

JK