

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23059-00-00
Spot: E2NWSWSE Sec/Twnshp/Rge: 8-11S-17W
990 feet from S Section Line, 2206 feet from E Section Line
Lease Name: ELMO CARMICHAEL Well #: 2
County: ELLIS Total Vertical Depth: 3570 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.62	209	0	140 SX CMT
PROD	5.5	3570	0	175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2010 8:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: ROGER L. COMEAU Company: LIBERTY OPER & COMPL, INC. Phone: (785) 434-4686

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - /1/4# flocele per sack - 500# hulls.
Bad casing.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2010 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

12/29/2010 - Fisher Well Service drilled down hole to 1110' - hole had bad casing.
12-30-2010 - Washed down from 700' to 1110'.
Pulled to 1088' out of bad casing .
Allied rigged to tubing and mixed and pumped 60 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 675'. Allied rigged to tubing and mixed and pumped 95 sxs to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 25 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 300#. S.I.P. 200#.
Rigged to 8 5/8" casing and pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3426	3429		Arbuckle
3348	3378		Cong

Remarks: ALLIED CEMENTING COMPANY-TICKET #30059.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

JAN 05 2011

Form CP-2/3

JAN 03 2011

KCC WICHITA