

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-01065-00-01  
Spot: NESESWSE Sec/Twnshp/Rge: 29-13S-17W  
337 feet from S Section Line, 1546 feet from E Section Line  
Lease Name: HUBIE (DREILING) Well #: 1  
County: ELLIS Total Vertical Depth: 3625 feet

Operator License No.: 31385  
Op Name: M G OIL INC  
Address: PO BOX 162  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3465		
SURF	8.625	186	0	130 SX
PROD	4.5	3584	0	150 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/16/2010 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: MARION COUNTS Company: M G OIL INC. Phone: (785) 483-4357

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.  
Perfed 4 1/2" casing at 1400' cwc at 250 sxs - Alt II.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/16/2010 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing rigged to 4 1/2" casing with a swedge and pumped 40 sxs 60/40 pozmix - 4% gel - followed with 10 sxs gel - followed with 175 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Max. P.S.I. 1000#. S.I.P. 500#.  
Rigged to 8 5/8" casing - pumped to 1000# with instant pressure.  
Shut in at 1000#.

Perfs:

Top	Bot	Thru	Comments
3521	3523		
3486	3490		
3426	3430		
3416	3418		
3396	3399		
3377	3380		

Remarks: ALLIED CEMENTING COMPANY-TICKET #33965.

Plugged through: CSG

District: 04

Signed

RECEIVED

DEC 23 2010

KCC WICHITA

(TECHNICIAN)

CM

Form CP-2/3

DEC 17 2010