

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20869-00-00
Spot: NENE Sec/Twnshp/Rge: 27-34S-34W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: LENEHAN Well #: 2-A
County: SEWARD Total Vertical Depth: 6775 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6415		WITH 2 SX CMT
CIBP		6570		
CIBP		6612		
SURF	8.625	1610		WITH 750 SX CMT
PROD	45	6773	1623	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/27/2010 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 6430' WITH 2 SX CMT. PLUG AT 1640' WITH 80 SX CMT. PLUG AT 580' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2010 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SHOT 4 1/2" CASING @ 2790', 2303', & 1972', UNABLE TO PULL, FINAL CUT @ 1623'. SET CIBP @ 6415' WITH 2 SX CMT. 1ST PLUG AT 1640' WITH 80 SX CMT. 2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 12 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6621	6636		ST LOUIS
6582	6587		ST LOUIS
6518	6526		ST LOUIS
6488	6492		ST LOUIS

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

JAN - 4 2011

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 21 2011

CONSERVATION DIVISION
WICHITA, KS Form CP-2/3