

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21555-00-00
Spot: NWSENW Sec/Twnshp/Rge: 23-26S-18W
1650 feet from N Section Line, 1700 feet from W Section Line
Lease Name: DERLEY Well #: 3
County: EDWARDS Total Vertical Depth: 4749 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4180		WITH 2 SX CMT
CIBP		4610		
SURF	8.625	330		WITH 250 SX CMT
PROD	5.5	4675	1504	WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2010 12:00 PM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: JEFF BURK Company: MID-CONTINENT ENERGY Phone: (316) 250-5655

Proposed Plugging Method: CIBP @ 4180' & 2 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2010 1:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4180' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1183' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4649	4653		

RECEIVED
DEC 14 2010
12-14-10
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED
DEC - 6 2010
KCC DODGE CITY

Form CR-273