

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22237-00-00
Spot: SWSNESW Sec/Twnshp/Rge: 15-18S-29W
1590 feet from S Section Line, 2100 feet from W Section Line
Lease Name: JAMES Well #: #1-15
County: LANE Total Vertical Depth: 4650 feet

Operator License No.: 31783
Op Name: MID-CONTINENT ENERGY OPERATIN
Address: 100 W 5TH ST STE 450
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	311		WITH 185 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/16/2010 7:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: LARRY HINDERLITER Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 340' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 12/16/2010 10:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 340' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
DEC 29 2010
KCC WICHITA

District: 01

RECEIVED
DEC 22 2010
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP 2/3