

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-21285-00-00  
Spot: NESWSENV Sec/Twnshp/Rge: 8-3S-41W  
2280 feet from N Section Line, 1660 feet from W Section Line  
Lease Name: ZWEYGARDT Well #: 1-8  
County: CHEYENNE Total Vertical Depth: 5675 feet

Operator License No.: 31783  
Op Name: MID-CONTINENT ENERGY OPERATIN  
Address: 100 W 5TH ST STE 450  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2011 1:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KIRBY Company: MID-CONTINENT ENERGY OPERA Phone: (918) 587-6363

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE  
Date/Time Plugging Completed: 01/13/2011 2:30 PM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 3460' w/25 sxs.  
2nd. Plug at 2675' w/100 sxs.  
3rd. Plug at 350' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

JAN 20 2011

KCC WICHITA

JAN 14 2011