

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-207-20436-00-00

Spot: NWSENWSW

Sec/Twnshp/Rge: 23-23S-13E

1890 feet from S Section Line,

835 feet from W Section Line

Lease Name: AJ HESSLER

Well #: 19

County: WOODSON

Total Vertical Depth: 2190 feet

Operator License No.: 6445

Op Name: MILLER BROS. OIL COMPANY, INC.

Address: 701 W 4TH
LEBO, KS 66856

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1724		
CIBP		1785		
SURF	7	107		50 SX
PROD	4.5	2190		100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/16/2010 8:00 AM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: DANIEL HORST

Company:

Phone: (620) 344-1518

Proposed Plugging Method: PULL ALL OF THE 4.5 CASING WE CAN. RUN 2 INCH BACK DOWN TO 1700' PUMP 20 SACKS CEMENT. COME UP TO BELOW THE DOUGLAS SET 10 SKS. COME UP ABOVE THE DOUGLAS SET 10 SKS. COME UP AND FILL FROM 200' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 07/08/2010 12:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700' pumped 20 sxs cement, pulled tubing out, shot casing @ 892' pumped 25 sxs cement, pulled casing to 150' circ. Cement to surface gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2140	2144		
1776	1782		
1750	1754		
1744	1748		
1699	1708		

RECEIVED

MH

KCC Chanute Dist. #3

RECEIVED
JAN 07 2011
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Mike Heffern

(TECHNICIAN)