

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20589-00-00  
Spot: N2SWSW Sec/Twnshp/Rge: 30-2S-29W  
990 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: ELBERT MAY B Well #: 1-30  
County: DECATUR Total Vertical Depth: 4070 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	343	0	225 SX
PROD	4.5	4069	0	250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/07/2011 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/07/2011 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 343' w/225 sxs cement.  
4 1/2" production casing set at 4069' w/200 sxs cement.  
Top of cement at 3230'.  
Perforated production casing at 2560' and 1850'.  
Ran tubing to 2628' - pumped 150 sxs cement mixed with 400# hulls.  
Pulled tubing to 1869' - pumped 120 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 4 1/2" production casing - pumped 20 sxs cement.  
Connected to 8 5/8" surface casing - pumped 65 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3838	3841		LKC "B"

RECEIVED  
JAN 24 2011  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS MAY POLLOW UNIT #1-1. SWIFT SERVICES CEMENTING COMPANY-TICKET #19385.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM