

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21014-00-00
Spot: NESESW Sec/Twnshp/Rge: 10-23S-15W
991 feet from S Section Line, 2176 feet from W Section Line
Lease Name: SMITH Well #: 1-B
County: PAWNEE Total Vertical Depth: 4152 feet

Operator License No.: 33490

Op Name: CONDOR ENERGY, INC.

Address: PO BOX 108
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	442		WITH 375 SX CMT
DVT		2172		WITH 150 SX CMT
PROD	4.5	4151	1042	WITH 150 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/29/2010 12:30 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 50' ABOVE PERFS & 4 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 470' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/29/2010 4:35 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SAND TO 3900' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1001' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 475' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
DEC 14 2010
12-14-10
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

DEC - 6 2010

KCC DODGE CITY

Form C-23

1/26/11