

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20629-00-00
Spot: NENESW Sec/Twnshp/Rge: 9-29S-19W
2360 feet from S Section Line, 2323 feet from W Section Line
Lease Name: CHILDRESS B Well #: 1
County: KIOWA Total Vertical Depth: 5105 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	325		WITH 190 SX CMT
PROD	4.5	5097	1250	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/04/2011 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: SAND 50' ABOVE PERFS WITH 4 SX CMT. PLUG AT 1270' WITH 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL
Date/Time Plugging Completed: 01/04/2011 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4970' WITH 4 SX CMT. 1ST PLUG AT 1250' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5024	5028		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Eric MacLaren

(TECHNICIAN)

KANSAS CORPORATION COMMISSION

RECEIVED
JAN 10 2011
KCC DODGE CITY

JAN 12 2011
RECEIVED
Form 672/3
1196/11