

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19862-00-00

Spot: SESENENW

Sec/Twnshp/Rge: 29-30S-16E

4236 feet from S Section Line, 2756 feet from E Section Line

Lease Name: UNIT 1

Well #: OW 2

County: WILSON

Total Vertical Depth: 305 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176

INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	150	0	150' is an estimate

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/01/2010 8:00 AM

Plug Co. License No.: 3830

Plug Co. Name: A X & P, INC.

Proposal Rcvd. from: J. J. HANKE

Company: A X & P, INC

Phone: (620) 920-0078

Proposed Plugging Method: DRILL OUT WHAT APPEARS TO BE A WOODED PLUG AFTER CUTTING OFF WHAT APPEARS TO BE 6 7/8" SURFACE PIPE AND SETTING 10" SURFACE PIPE TO SURFACE, CEMENTING W/ 10 SX. DRILL DOWN, RUN 2" AND CEMENT.

Plugging Proposal Received By: STEVE KORF

WitnessType: NONE

Date/Time Plugging Completed: 09/02/2010 8:00 AM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

10" surface pipe was set over the old surface pipe using 10 sacks of cement. The well was then drilled to 305' where the bit hit hard. A cement string was then lowered to 305' and the well pumped full of cement. A total of 147 sacks of portland cement were used to plug well.

RECEIVED

JAN 12 2011

AMD

KCC Chanute Dist. #3

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning

(TECHNICIAN)

RECEIVED

Form CP-2/3

JAN 14 2011

KCC WICHITA