

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21041-00-00
Spot: NENWSE Sec/Twnshp/Rge: 10-18S-1E
2309 feet from S Section Line, 1663 feet from E Section Line
Lease Name: SCULLY W Well #: 8-10
County: MARION Total Vertical Depth: 3325 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226		150 SXS CMT
PROD	4.5	3323		345 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2010 10:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P. BANDY Company: _____ Phone: (620) 628-4428

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2010 11:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

12/15/2010 CYCLONE DROPPED SAND. THEY TAGGED SAND @ 3162' AND CAPPED IT W/5 SX. 12/16/10 CYCLONE TAGGED CEMENT CAP @ 3109'. THEY THEN PUSHED A RUBBER PLUG TO 318' AND DROPPED SAND ON IT TO FILL UP TO 300'. CONCRETE PRODUCTS OF HILLSBORO DUMPED 1 YD OF SLURRY MIX TO FILL UP 4 1/2" CASING. TK #46153 FOR 2 YDS SLURRY MIX. TEPE WILL DIG OUT BRAYDEN HEAD TOMORROW AND CUT OFF TO CHECK CEMENT ON BACKSIDE. 12/17/10 CYCLONE OUT DIGGING OUT BRAYDEN HEAD. CEMENT TO SURFACE ON BACKSIDE.


Perfs:

Top	Bot	Thru	Comments
3248	3256	CSG	
3223	3232	CSG	
3222	3225	CSG	

Remarks: PBTD @ 3279, PERFS @ 3223-32 & 3248 - 56 SQUEEZED OFF AND REPERFED @ 3222 - 25

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)

RECEIVED
JAN 03 2011
KCC WICHITA
Form CP-2/3
1/26/11

1/26