

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06665-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 30-21S-8W
2330 feet from S Section Line, 2291 feet from E Section Line
Lease Name: KEELEY ESTATE Well #: 1
County: RICE Total Vertical Depth: 3451 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		150 SX COMMON CMT
T1	2	3370		
L1	3	3310		200 SX
PROD	4.5	3449		75 SX COMMON CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/29/2010 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: JOE BURDETT Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 960-5612

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 12/29/2010 1:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS OUT OF WELL. LOWER TUBING DOWN TO TAG BOTTOM. PULL UP TO 3410' AND PUMP 30 SX'S CEMENT. PULL TUBING OUT OF HOLE. PERFORATE AT 700'--4 HOLES. RUN TUBING BACK DOWN TO 700' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND CONNECT ON TO 3" LINER AND PRESSURE UP TO 600#'S--SHUT IN.

Perfs:

Top	Bot	Thru	Comments
3358	3365		MISSISSIPPI

Remarks: 60-40 POZ, 4% GEL. COPELAND CEMENT #C-35197. GRESSEL PERF TICKET #0764.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

(TECHNICIAN)

RECEIVED

JAN 11 2011

Form CP-2/3

KCC WICHITA

1/26/11