

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21037-00-00
Spot: S2SE Sec/Twnshp/Rge: 18-33S-21W
639 feet from S Section Line, 1318 feet from E Section Line
Lease Name: MCMINIMY A Well #: 1-18
County: CLARK Total Vertical Depth: 5550 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	745		WITH 450 SX CMT
PROD	4.5	5530	0	WITH 75 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/20/2010 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: KAMERON WILSON Company: BEREXCO LLC Phone: (316) 772-2971

Proposed Plugging Method: PUMP 20 SX CMT AT 5300' OR SET CIBP & 2 SX CMT. PUMP 50 SX CMT & HULLS AT 2600'. WAIT & TAG CMT. PLUG AT 780' WITH 15 SX GEL, 200# HULLS & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: PARTIAL
Date/Time Plugging Completed: 12/20/2010 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

12/17/10: PUMPED 200# HULLS & 50 SX CMT AT 5300'. PUMPED 200# HULLS & 70 SX CMT AT 2600'. 12/20/10: TAGGED CMT AT 1000'. 1ST PLUG AT 780' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT. CMT CIRCULATED. PRESSURED BACKSIDE TO 200# WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5358	5372		CHESTER

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
DEC 29 2010
KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
DEC 22 2010
KCC DODGE CITY

Form 2/3
1/26/11