

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23646-00-00  
Spot: S2SWNW Sec/Twnshp/Rge: 7-6S-19W  
2310 feet from N Section Line, 750 feet from W Section Line  
Lease Name: BROBST Well #: 1  
County: ROOKS Total Vertical Depth: 3572 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213	0	150 SX CMT.
T1	2.875	3550		
PROD	5.5	3568	0	450 SX CMT.

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2010 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 4% gel - 400# hulls - 14 sxs gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/22/2010 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 14 sxs gel spacer and 175 sxs cement with 200# hulls.  
Max. P.S.I. 700#. S.I.P. 500#.  
Backside full of cement.  
Note: Alt II circulated cement bottom to surface.

Perfs:

Top	Bot	Thru	Comments
3562	3564		
3556	3558		
3502	3504		
3463	3466		
3355	3358		
3302	3305		

RECEIVED  
JAN 03 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

✓ 1/26/11

DEC 29 2010