

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22331-00-00  
Spot: W2NENE Sec/Twnshp/Rge: 5-7S-20W  
660 feet from N Section Line, 990 feet from E Section Line  
Lease Name: LESAGE B Well #: 2  
County: ROOKS Total Vertical Depth: 3675 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	252	0	w/175 sxs cmt
PROD	4.5	3721	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2010 12:00 PM  
Plug Co. License No.: 33137 Plug Co. Name: GASCHLER WELL SERVICE LLC  
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
CIBP at 3675' and 3200'.  
Squeezed at 2118' - 2150' w/50 sxs and 1090' w/300 sxs.  
Perforated at 750' and 250'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2010 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3100' - pumped 110 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1600' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.  
Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.

Perfs:

Top	Bot	Thru	Comments
3694	3702		
3650	3652		
3642	3644		
3640	3641		
3622	3625		
3615	3618		
3607	3610		
3516	3517		

Remarks: ALLIED CEMENTING COMPANY-TICKET #34076.

Plugged through: TBG

RECEIVED

DEC 31 2010  
12.30.10  
KCC WICHITA

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

C.M.

DEC 29 2010

Form CP-2/3  
*11/26/10*