

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20262-00-00
Spot: N2SENENW Sec/Twnshp/Rge: 32-14S-10E
850 feet from N Section Line, 2310 feet from W Section Line
Lease Name: ELDRIDGE Well #: 3-32
County: WABAUNSEE Total Vertical Depth: 3243 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LA
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	321		185 SX CMT
T1	2.875	3233		
PROD	5.5	3241		125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2010 10:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN CABLE Company: LARSON ENGINEERING, INC. DBA Phone: (785) 445-2888

Proposed
Plugging
Method:

As directed by District staff.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 12/17/2010 3:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

SET CAST IRON BRIDGE PLUG AT 3200'. PERFORATED THE 5.5" CASING AT 1600'. RAN 2.5" TUBING TO 1600' AND PUMPED A GEL SPACER FOLLOWED BY 25 SACKS OF CEMENT. PERFORATED THE 5.5" CASING AT 1100' TO TRY TO RETRIEVE IT. THE 5.5" CASING WOULD NOT MOVE. PERFORATED THE 5.5" CASING AT 584' AND WAS ABLE TO RETRIEVE 584' OF 5.5". RAN 2.5" TUBING TO 350' AND LOADED THE HOLE WITH GEL FOLLOWED BY 100 SACKS OF CEMENT. PULLED THE 2.5" TUBING OUT AND TOPPED THE WELL OFF.

Perfs:

Top	Bot	Thru	Comments
3241	3243		

RECEIVED

FEB 15 2011 TCH
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 17 2011

02-17-11

KCC WICHITA