

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20685-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 5-16S-10W
981 feet from S Section Line, 2193 feet from E Section Line
Lease Name: ELSIE OSHEL Well #: 1
County: ELLSWORTH Total Vertical Depth: 3327 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3320		
SURF	8.625	350		200 SX
PROD	4.5	3324		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2011 10:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES, SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/23/2011 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT TO GET TO TD. HAD A BIT ON TUBING --GOT THRU 2 TO 3 PLACES AFTER TURNING ON, FINALLY GOT TO 2138'--COULD NOT GET ANY DEEPER. PULL 1 JT. TUBING OUT TO APPROX 2130'--PUMPED 50 SX'S CEMENT. PULL TUBING OUT OF HOLE. PERFORATE AT 1300', 1000', AND 400'. RUN TUBING BACK DOWN TO 1300' AND PUMP 35 SX'S CEMENT WITH SOME COTTON HULLS TRAILING IN. PULL TUBING TO 1000' AND PUMP 35 SX'S CEMENT WITH SOME COTTON HULLS TRAILING IN. PULL TUBING TO 400' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON CASING AND ATTEMPT TO SQUEEZE CEMENT OUT OF SURFACE CASING. PRESSURED UP TO 400#S. CONNECTED ON TO SURFACE CASING AND PUMPED APPROX. 50 SX'S--PRESSURED UP AND STOPPED. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3314	3319	CSG	
3150	3154	CSG	
3098	3108	CSG	
2944	2954	CSG	
2762	2768	CSG	

Remarks: 60-40 POZ, 4% GEL. SWIFT SERVICES #19559. PIONEER SVC'S PERF TICKET #33057.

Plugged through: TBG

DENIED TA STATUS DUE TO LENGTH OF TIME.

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED

MAR 14 2011

Form CP-2/3

KCC WICHITA

3/18