

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22638-00-00  
Spot: SWNWSENE Sec/Twnshp/Rge: 13-19S-10W  
1750 feet from N Section Line, 1100 feet from E Section Line  
Lease Name: LONG Well #: 2-13  
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	314		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2011 8:00 AM

Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: STEVE STEVENSON Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 35-ARB, 35-1200, 35-850, 35-370, 25-60, 20-RH, 15 - MH

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: NONE

Date/Time Plugging Completed: 02/28/2011 12:45 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

THE DRILL PIPE WAS RUN OPEN END TO TOP OF ARB, WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 1200', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 370', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 60', WHERE CMT WAS CIRCD TO SURFACE. THE RAT HOLE WAS CIRCD WITH 20 SKS OF CMT. THE MOUSE HOLE WAS CIRCD WIT H15 SKS OF CMT.

Remarks: ALLIED CMTG #38710 60/40 4% GEL

Plugged through: DP

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

MAR 03 2011

Form CP-2/3

KCC WICHITA

3/18

SK