

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-02243-00-00
Spot: NWNENE Sec/Twnshp/Rge: 2-17S-10W
4922 feet from S Section Line, 757 feet from E Section Line
Lease Name: STRATMANN Well #: 2
County: ELLSWORTH Total Vertical Depth: 3288 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3200		
SURF	10.75	232		
LI	5.5	3270		
PROD	7	3272		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2011 12:00 PM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES, SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed Plugging Method: SEE BELOW

[Empty box for proposed plugging method details]

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/21/2011 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 3200' AND CAP WITH 2 SX'S CEMENT. PERFORATE @ 1250', 950' AND 280'. RUN TUBING TO 1250' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 950' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 280' AND CIRCULATE CEMENT TO SURFACE. CLOSE VALVE ON 5.5"--PRESSURED UP TO 400#"S. PUMPED 15 SX'S CEMENT DOWN CONNECTION ON SURFACE CASING UNTIL PRESSURED UP. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3272	3288	OH	OHIO

Remarks: 60-40 POZ, 4% GEL. SWIFT SERVICES #20147. PIONEER WIRELINE #33055.
DENIED TA DUE TO HIGH FLUID LEVEL.

Plugged through: TBG

RECEIVED
MAR 14 2011
KCC WICHITA

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK

2/18